

POLICY REPORT

Report Date: February 26, 2019

Contact: Karen Hoese Contact No.: 604.871.6403

RTS No.: 13047

VanRIMS No.: 08-2000-20 Meeting Date: March 12, 2019

TO: Vancouver City Council

FROM: General Manager of Planning, Urban Design and Sustainability

SUBJECT: Rezoning: 976 West 52nd Avenue and 6822-6868 Oak Street

RECOMMENDATION

A. THAT the application by Listraor (West 52nd) Homes Ltd., the registered owner, to rezone 976 West 52nd Avenue and 6822-6850 Oak Street [Lots 1, 2 3, and 4, all of Block 880, District Lot 526, Plan 11706; PIDs: 009-061-720, 009-061-789, 009-061-797, 009-061-801 respectively] and 6868 Oak Street [PID: 010-031-898; Lot 5 of Block 880, District Lot 526, Plan 9628] all from RS-1 (Single Family) District to RM-8AN (Multiple Dwelling) District, be referred to a Public Hearing, together with the recommendation of the General Manager of Planning, Urban Design and Sustainability to approve the application in principle, subject to the Conditions of Approval contained in Appendix B;

FURTHER THAT the Director of Legal Services be instructed to prepare the necessary amending by-law generally in accordance with Appendix A for consideration at the Public Hearing.

B. THAT, subject to the enactment of the amending By-law, the Subdivision By-law be amended generally as set out in Appendix C;

FURTHER THAT the Director of Legal Services be instructed to bring forward the amendment to the Subdivision By-law at the time of enactment of the amending By-law.

- C. THAT Recommendations A and B be adopted on the following conditions:
 - (i) THAT the passage of the above resolutions creates no legal rights for the applicant or any other person, or obligation on the part of the City and any expenditure of funds or incurring of costs is at the risk of the person making the expenditure or incurring the cost;

- (ii) THAT any approval that may be granted following the public hearing shall not obligate the City to enact a by-law rezoning the property, and any costs incurred in fulfilling requirements imposed as a condition of rezoning are at the risk of the property owner; and
- (iii) THAT the City and all its officials, including the Approving Officer, shall not in any way be limited or directed in the exercise of their authority or discretion, regardless of when they are called upon to exercise such authority or discretion.

REPORT SUMMARY

This report recommends a plan amendment to the Zoning and Development By-Law for the site located at 976 West 52nd Avenue and 6822-6868 Oak Street. The proposed amendment would rezone the site from RS-1 (One-Family Dwelling) District to RM-8AN (Multiple Dwelling) District, to allow for a townhouse development with a floor space ratio (FSR) up to 1.2.

As part of the implementation of the *Cambie Corridor Plan*, sites designated for townhouse uses outside of the first stage of the City's infrastructure upgrades will be considered through privately-initiated rezoning applications, so long as infrastructure upgrades are secured as conditions of rezoning.

Staff have assessed the application and conclude that it meets the intent of the *Cambie Corridor Plan*. Staff recommend that the application be referred to a Public Hearing, with the recommendation of the General Manager of Planning, Urban Design and Sustainability to approve it in principle, subject to the Public Hearing, and conditions contained within Appendix B.

COUNCIL AUTHORITY/PREVIOUS DECISIONS

Relevant Council policies for this site include:

- Cambie Corridor Plan (2018)
- Cambie Corridor Utilities Servicing Plan (2018)
- RM-8, RM-8A, RM-8N and RM-8AN Districts Schedule (2018)
- RM-8A and RM-8AN Guidelines (2018)
- Green Buildings Policy for Rezonings (2010, last amended 2017)
- Community Amenity Contributions Through Rezonings (1999, last amended 2018)

REPORT

Background/Context

1. Site and Context

The subject site consists of five legal parcels located at the southeast corner of Oak Street and West 52nd Avenue (see Figure 1). The total site size is 3,844 sq. m (41,377 sq. ft.), with a combined frontage of approximately 87 m (286 ft.) along Oak Street and a depth of 44 m (145 ft.). The site is currently zoned RS-1 and developed with single-family homes without secondary suites. A similar single-family home neighbourhood context surrounds the site.




Figure 1: Location Map - Site and Context

2. Policy Context

In 2018, Council adopted the final *Cambie Corridor Plan* (the "Plan"). The subject site is located within the Langara neighbourhood, which is characterized by its existing low-density residential character. The Plan calls for new family-oriented housing opportunities, in the form of townhouses, to be introduced in transition areas off Cambie Street, West 49th Avenue, and along Oak Street.

The site is guided by Section 4.4.7 of the Plan, which generally supports residential uses in townhouse form up to three storeys in height at the street and a density of up to 1.2 FSR. In this area, the Plan strives to accommodate improvements for pedestrians. A road dedication along Oak Street and an expanded setback along the southern property line are required to achieve public realm improvements on Oak Street and an east-west pedestrian connection through the site.

3. Plan Implementation and Utilities Servicing Plan

The Plan is a framework to guide change and growth in the area over the next 30 years. By 2041, the Corridor's population is anticipated to more than double, with over 30,000 new homes, making it the biggest growth area outside of Downtown.

The Plan identifies over 1,100 single-family lots for future townhouses, creating opportunities for up to 8,200 units of this much-needed ground-oriented housing type. Due to limitations in infrastructure capacity in the Corridor, City-initiated rezonings for townhouses will be phased to align with scheduled infrastructure upgrades as identified in the Cambie Corridor *Utilities* Servicing Plan (USP), which was endorsed by Council in July 2018. The first phase of City rezonings (in the Stage 1 area) was approved by Council in September 2018. See Appendix D for further details on the USP phasing.

The sequencing of City-delivered utility design and construction will happen between 2019-2022 (Stage 1) and 2023-2026 (Stage 2). The specific timing of Stage 3 upgrades is undetermined at present. Future phases of City-initiated rezoning of townhouse areas will be coordinated with the timing of future infrastructure upgrades. In the meantime, townhouse development outside of Stage 1 can be considered through developer-initiated rezonings (such as this application), which will allow a case-by-case determination of required off-site utility upgrades.

Strategic Analysis

1. Simplified Rezoning Process

To facilitate the delivery of family-friendly townhouse units to the market while the phased roll-out of the USP is taking place, the City has implemented a simplified process for privately-initiated rezoning for townhouses. Rather than rezoning townhouse sites to a site-specific Comprehensive Development (CD) District, the recently approved RM-8A/RM-8AN Districts Schedule will be used as the designated zone. This will provide the same certainty on the built form for residents and applicants that the City-initiated rezoning provides, and will also streamline the review process.

The RM-8A and RM-8AN Districts were approved by Council in 2018, along with associated design guidelines, and apply specifically to the Cambie Corridor and Grandview-Woodland neighbourhoods. The zone includes a unit size requirement to ensure greater unit size mix with a greater variety of price points of new townhouse units, as well as more flexible development options for smaller lots. The RM-8AN District differs from the RM-8A District because it requires noise mitigation for dwelling units close to arterial streets. As the subject fronts an arterial street, it will be rezoned to the RM-8AN.

Since the intent of the rezoning is primarily to secure servicing upgrades and minor and/or specific transportation upgrades identified in the Plan, no architectural drawings are required at the rezoning stage. The form of development will be reviewed through a subsequent development permit process. All proposals will need to meet the intent and regulations of the RM-8A/RM-8AN Districts. No Urban Design Panel review is necessary for this project due to the small scale of the buildings and comprehensive design guidelines developed to accompany the RM-8A and RM-8AN Districts Schedule.

2. Tenants

The site is currently zoned RS-1 and developed with single-family homes without secondary suites. There are no long-term tenants on site. The five homes are currently occupied by tenants under short-term leases who are aware of this rezoning application. The *Tenant Relocation and Protection Policy* does not apply to redevelopment of "secondary" rental stock, including single-family houses, basement suites, duplexes, or individually-rented condos; therefore, a *Tenant Relocation Plan* is not required.

3. Transportation, Parking and Servicing

Parking, loading and bicycle spaces must be provided and maintained according to the provisions of the Vancouver Parking By-law and will be reviewed at time of the development permit application when proposal drawings are submitted. Through this application, conditions of approval include a road dedication along Oak Street. Through this application, staff are seeking a Statutory Right-of-Way (SRW) along the southern property line in order to secure a secondary active link for pedestrians. This requirement is in accordance with the Cambie Corridor Public Realm Plan. Lastly, off-site servicing requirements are also being secured through a services agreement. Engineering rezoning conditions are included in Appendix B.

4. Environmental Sustainability

The *Green Buildings Policy for Rezonings* (amended by Council on May 2, 2018) requires that residential rezoning applications satisfy either the near zero emission buildings or low emissions green buildings conditions within the policy. These new requirements are mandatory for all rezoning applications received on or after May 1, 2017.

For small buildings, such as townhomes and those considered Part 9 under the Building By-law, the requirements of the policy have been adapted to match the building scale. These requirements are prescribed in the *Green Buildings Policy for Rezonings – Process and Requirements* administration bulletin.

As part of the rezoning, the applicant has submitted a letter of commitment to meet the policy, and to provide further documentation at the development permit application stage. Conditions have been included in Appendix B to ensure that policy requirements are satisfied.

PUBLIC INPUT

Public Notification

A rezoning information sign was installed on the site on November 27, 2018. Approximately 375 notification letters were distributed within the neighbouring area on or about December 13, 2018. Notification and application information was provided on the City of Vancouver Rezoning Centre webpage (Vancouver.ca/rezapps).

The requirement for a public open house is waived for these simplified townhouse rezoning applications as extensive public engagement was undertaken during the *Cambie Corridor Plan* process to inform land use changes. Opportunities for public input regarding specific building design for this site will be available at the development permit stage in accordance with the standard City notification process.

PUBLIC BENEFITS

The Cambie Corridor Public Benefit Strategy (see Appendix E) identifies public amenities and infrastructure to support growth in the area, including both short-term and long-term priorities, in response to changes in land use and density. This application addresses public benefits as follows:

Development Cost Levies (DCLs)

This site will be subject to both the City-wide DCL and the City-wide Utilities DCL, which are payable at time of building permit issuance.

Density Bonus Zone Contributions (DBZ)

Rezonings to the RM-8A and RM-8AN district schedules, such as the subject site, are exempt from paying CACs. The rezoned site will be subject to a Density Bonus Zone (DBZ) contribution on the net additional density, payable at building permit issuance. Further information on DCLs and DBZs can be found in Appendix D.

FINANCIAL IMPLICATIONS

As noted in the section on Public Benefits, the site will be subject to a density bonusing contribution, the City-wide DCL, and the City-wide Utilities DCL.

Based on the rates in effect as of September 30, 2018, a density bonusing contribution of approximately \$1,137,840 would be expected from the development should it achieve the maximum density of 1.2 FSR.

Based on rates in effect as of September 30, 2018, total DCLs of approximately \$324,724 would be expected from this development should it achieve the maximum 1.2 FSR.

Approval and timing of specific projects to be funded from these contributions will be brought forward as part of capital planning budget process.

CONCLUSION

Staff have reviewed the application to rezone the site at 976 West 52nd Avenue and 6822-6868 Oak Street from RS-1 to RM-8AN to facilitate the development complying with the provisions of the RM-8AN District Schedule, and conclude that the rezoning application is consistent with the *Cambie Corridor Plan*.

The General Manager of Planning, Urban Design and Sustainability recommends that the rezoning application be referred to a Public Hearing with a recommendation that, subject to the Public Hearing, the rezoning application be approved in principle, subject to the applicant fulfilling the conditions of approval in Appendix B.

976 West 52nd Avenue and 6822-6868 Oak Street

DRAFT By-law to Amend Zoning and Development By-law No. 3575 to rezone an area from RS-1 to RM-8AN

Note: A By-law will be prepared generally in accordance with the provisions listed below, subject to change and refinement prior to posting.

Zoning District Plan Amendment

- 1. This By-law amends the Zoning District Plan attached as Schedule D to By-law No. 3575, and amends or substitutes the boundaries and districts shown on it, according to the amendments, substitutions, explanatory legends, notations, and references shown on the plan marginally numbered [] attached as Schedule A to this By-law, and incorporates Schedule A into Schedule D to By-law No. 3575.
- 2. The area shown within the heavy black outline on Schedule A is rezoned and moved from the RS-1 District Schedule to the RM-8AN District Schedule.

Schedule A 1.3 W 51ST AV OAK ST D Ε F W 52ND AV FREMLIN ST W 53RD AV The properties outlined in black () are rezoned: From RS-1 RM-8AN map: 1 of 1 RZ - 976 W 52nd Avenue & 6822-6868 Oak Street scale: NTS date: 2018-11-27 **City of Vancouver**

976 West 52nd Avenue and 6822-6868 Oak Street CONDITIONS OF APPROVAL

Note: If the application is referred to a public hearing, these Conditions of Approval will be referenced in the Summary and Recommendations included in the hearing agenda package. Any changes to the conditions approved by Council will be contained in its decision. Applicants are advised to consult the public hearing minutes for any changes or additions to these conditions.

PART 1: CONDITIONS OF APPROVAL OF THE FORM OF DEVELOPMENT

THAT, prior to approval by Council of the form of development, the applicant shall obtain approval of a development application by the Director of Planning who shall have particular regard to the following:

Sustainability

1. All new buildings in the development will meet the requirements of the *Green Buildings Policy for Rezonings* (amended May 2, 2018), including all requirements for Near Zero Emissions Buildings (i.e. Passive House certified or alternate near zero emissions standard approved by the Director of Sustainability), or Low Emissions Green Buildings. The requirements for Low Emissions Green Buildings are summarized at http://guidelines.vancouver.ca/G015.pdf.

Note to Applicant: The applicant will be required to demonstrate that the development is on track to achieve the above requirements at each stage of permit. For more detail on the above requirements and what must be submitted at each stage, refer to the most recent bulletin *Green Buildings Policy for Rezonings – Process and Requirements* (amended April 28, 2017 or later).

PART 2: CONDITIONS OF BY-LAW ENACTMENT

THAT, prior to enactment of the amending By-law, the registered owner shall on terms and conditions satisfactory to the Director of Legal Services, the General Manager of Planning, Urban Design and Sustainability, the General Manager of Engineering Services and the General Manager of Arts, Culture and Community Services (or successors in function), as necessary, and at the sole cost and expense of the owner/developer, make arrangements for the following:

Engineering

- 1. Consolidation of Lots 1 to 4, all of Block 880, District Lot 526, Plan 11706; and Lot 5 of Block 880, District Lot 526, Plan 9628 to create a single parcel and subdivision of that site to result in the dedication of the westerly 7.9 ft. (2.408 m) for road purposes.
 - A subdivision plan and application to the Subdivision and Strata Group is required. For general information see the subdivision website at: http://vancouver.ca/home-property-development/apply-to-subdivide-or-join-properties.aspx.
- 2. Provision of a 4.4 m (15 ft.) wide setback from the south property line with a surface Statutory Right of Way (SRW) over the 2.6 m (9 ft.) adjacent the south property line for a

secondary active link as per the Cambie Corridor Public Realm Plan. The SRW shall be free of any encumbrances at grade.

Note to Applicant: Setbacks under 0.6 m (2 ft.) will not be registered as an SRW, but must be free of encumbrances.

- 3. Provision of a Services Agreement to detail the on and off-site works and services necessary or incidental to the servicing of the site (collectively called the "services") such that they are designed, constructed and installed at no cost to the City and all necessary street dedications and rights of way for the services are provided. No development permit for the site will be issued until the security for the services is provided.
 - (a) Provision for the installation of a fire hydrant fronting the development on Oak Street Arrangements to the satisfaction of the General Manager of Engineering Services and the Director of Legal Services will be required to secure payment for the new hydrant installation. The developer is responsible for 100% of the cost.
 - (b) Provision of adequate sewer (storm and sanitary) service requires to meet the demands of the project including the following:
 - (i) Implementation of development(s) at 976 West 52nd Avenue and 6822-6868 Oak Street requires the following in order to improve sewer flow conditions:
 - a. Local servicing upgrade: Separate existing combined sewer on
 Oak Street from West 52nd Avenue to West 54th Avenue (approx.
 261 m). Storm sewer is anticipated to be 525 mm diametre and
 sanitary sewer to be 200 mm.
 - b. Off-site servicing upgrade: none.

Note to Applicant: The West 54th Avenue Trunk requires upgrading to support the growth in the catchment area. The City is targeting delivery of the upgraded trunk for Year 3 of the DCL program (approximately 2021) to align with expected development occupancies. The applicant is to regularly inform the Integrated Water Management (IWM) Branch (Utilities.Servicing@Vancouver.ca) of their updated construction and occupancy schedule as the development progresses. This will assist the IWM Branch in scheduling the trunk delivery. If the IWM Branch is not kept informed of the developer's schedule, the occupancy permit approval may not meet the developer's schedule.

The post-development 10-year flow rate discharged to the storm sewer shall be no greater than the 10-year pre-development flow rate. The pre-development estimate shall utilize the 2014 IDF curves, whereas the post-development estimate shall utilize the 2100 IDF curves to account for climate change.

Applicant's Engineer to submit design brief, calculations and/or model, and design drawings to the City. All submittals, including upgrade design drawings (90% design stage or better), are required to be reviewed and accepted by the City Engineer prior to development permit issuance.

Development is to be serviced to the proposed storm and sanitary sewers on Oak Street.

- (c) Applicant is to submit a Hydrogeological Study to be reviewed and accepted by a City Engineer. The Study shall include a Groundwater Management Plan and an Impact Assessment, respectively, to demonstrate that no groundwater is to be discharged to the City's sewer network post construction, and that groundwater extraction/diversion shall have no significant negative impacts. The final Hydrogeological Study is required prior to rezoning enactment.
- (d) Provision of new or replacement duct banks adjacent to the development site that meet current City standards. Duct banks are to consist of electrical and communication ducts sized to meet City needs in a configuration acceptable by the General Manager of Engineering Services and in conformance with applicable electrical codes and regulations. A detailed design will be required prior to the start of any associated street work.

Note to Applicant: As-constructed documentation will be required that includes photographic and measured evidence of the installed number of conduits, their final locations and depths.

- (e) Provision of funding for the installation of parking regulatory signage on streets adjacent to the site to the satisfaction of the General Manager of Engineering Services.
- (f) Provision of a minimum 1.53 m (5 ft.) light broom finish saw cut concrete sidewalk on the south property line of the site in this SRW area. The remainder of the SRW is intended for public realm amenities for the mid-block connection including benches, landscape and pedestrian lighting.
 - Note to Applicant: The intention is for the adjacent site to provide a matching mid-block connection once it redevelops in order to achieve a total paved pathway width of 3.05 m (10 ft.).
- (g) Provision of a 1.83 m (6 ft.) sod grass front boulevard with trees and 2.44 m (8 ft.) light broom finish saw cut concrete sidewalk on Oak Street frontage.
- (h) Provision of 2.44 m (8 ft.) sod grass front boulevard with trees and minimum 2.14 m (7 ft.) light broom finish saw cut concrete sidewalk on West 52nd Avenue frontage.
- (i) Provision of a standard concrete lane crossing including new curb returns and curb ramps on both sides of the lane entry as per City standard.

- (j) Provision of new curb ramps on the southeast corner at the intersection of West 52nd Avenue and Oak Street, as per City standard.
- (k) Consideration of upgraded street lighting adjacent to the site to current standards including a review of the existing lighting to determine its adequacy and a lighting design as required.
- 4. Provision of all utility services to be underground from the closest existing suitable service point. All electrical services to the site must be primary with all electrical plant, which include, but are not limited to, System Vista, Vista switchgear, pad mounted transformers, LPT and kiosks (including non-BC Hydro kiosks), and are to be located on private property with no reliance on public property for placement of these features.

In addition, there will be no reliance on secondary voltage from the existing overhead electrical network on the street right-of-way. Any alterations to the existing overhead/underground utility network to accommodate this development will require approval by the Utilities Management Branch.

Note to Applicant: Please ensure that in your consultation with B.C. Hydro an area has been defined within the development footprint to accommodate such electrical plant. Please confirm that this space has been allocated and agreement between both parties has been met.

Sustainability

5. For buildings containing 20 units or more, the applicant will enter into an agreement with the City, on terms and conditions acceptable to the Director of Sustainability and the Director of Legal Services, that requires the future owner of the building to report energy use data, on an aggregated basis, for the building as a whole and certain common areas and building systems. Such an agreement will further provide for the hiring of a qualified service provider to assist the building owner for a minimum of three years in collecting and submitting energy use data to the City.

Environmental Contamination

- 6. If applicable:
 - (a) Submit a site profile to Environmental Services (Environmental Protection);
 - (b) As required by the Manager of Environmental Services and the Director of Legal Services in their discretion, do all things and/or enter into such agreements deemed necessary to fulfill the requirements of Section 571(B) of the Vancouver Charter; and
 - (c) If required by the Manager of Environmental Services and the Director of Legal Services in their discretion, enter into a remediation agreement for the remediation of the site and any contaminants which have migrated from the site on terms and conditions satisfactory to the Manager of Environmental Services, the General Manager of Engineering Services and Director of Legal Services, including a Section 219 Covenant that there will be no occupancy of any

buildings or improvements on the site constructed pursuant to this rezoning until separate Certificates of Compliance satisfactory to the City for the on-site and off-site contamination, issued by the Ministry of Environment, have been provided to the City.

Note to Applicant: Where the Director of Legal Services deems appropriate, the preceding agreements are to be drawn, not only as personal covenants of the property owners, but also as registerable charges pursuant to the Land Title Act.

The preceding agreements are to be registered in the appropriate Land Title Office, with priority over such other liens, charges and encumbrances affecting the subject site as is considered advisable by the Director of Legal Services, and otherwise to the satisfaction of the Director of Legal Services prior to enactment of the By-law and at no cost to the City.

The preceding agreements shall provide security to the City including indemnities, warranties, equitable charges, letters of credit and withholding of permits, as deemed necessary by and in a form satisfactory to the Director of Legal Services. The timing of all required payments, if any, shall be determined by the appropriate City official having responsibility for each particular agreement, who may consult other City officials and City Council.

976 West 52nd Avenue and 6822-6868 Oak Street DRAFT CONSEQUENTIAL AMENDMENTS


DRAFT AMENDMENT TO THE SUBDIVISION BY-LAW NO. 5208

Council amends Schedule A of the Subdivision By-law in accordance with the plan labelled Schedule A and attached to and forming part of this By-law, by deleting the following properties from the RS-1, RS-3, RS-3A, RS-5 and RS-6 maps forming part of Schedule A of the Subdivision By-law:

- (a) PID 009-061-720; Lot 1, Block 880, District Lot 526, Plan 11706;
- (b) PID 009-061-789; Lot 2, Block 880, District Lot 526, Plan 11706;
- (c) PID 009-061-797; Lot 3, Block 880, District Lot 526, Plan 11706;
- (d) PID 009-061-801; Lot 4, Block 880, District Lot 526, Plan 11706; and
- (e) PID 010-031-898; Lot 5, Block 880, District Lot 526, Plan 9628.

976 West 52nd Avenue and 6822-6868 Oak Street ADDITIONAL INFORMATION

1. Public Utility Infrastructure Upgrades: Staging of Upgrades



2. Public Benefits Information

Development Cost Levies (DCLs)

Development Cost Levies (DCLs) collected from development help pay for facilities made necessary by growth, including parks, childcare facilities, replacement housing (social/non-profit housing) and engineering infrastructure.

DCL rates are subject to future adjustment by Council including annual inflationary adjustments. DCLs are payable at building permit issuance based on rates in effect at that time. A development may qualify for 12 months of in-stream rate protection from DCL rate increases, provided that an application has been received prior to the rate adjustment. See the City's DCL Bulletin for details on DCL rate protection.

Community Amenity Contributions (CACs)

On December 19, 2018, City Council approved a CAC exemption for any sites being rezoned to the RM-8A and RM-8AN district schedules. The 'Cambie Corridor: Townhouse CAC Target' of \$55 per sq. ft. was removed concurrently with this policy amendment, effectively replaced with an equivalent density bonus contribution under the new district schedule.

The amendment was initiated to align City processes and to prevent the unintentional over-contribution from townhouse rezonings in the Cambie Corridor. This approach is consistent with townhouse developments in areas that have been already been pre-zoned by the City and can be considered directly through a development permit process.

Density Bonus Zone Contributions (DBZ)

Density bonusing is a zoning tool that permits developers to build additional floor space in exchange for affordable housing or other amenities such as community centres, libraries, parks, childcare centres.

DBZ rates are subject to future adjustment by Council, including annual inflationary adjustments. DBZs are payable at building permit issuance based on rates in effect at that time. A development may qualify for in-stream rate protection from DBZ rate increases, provided that an application has been received prior to a rate adjustment. See the City's DBZ Bulletin for additional information on DCZs.

3. Cambie Corridor Public Benefits Strategy (PBS)

The Cambie Corridor PBS (see Appendix E), approved on May 1, 2018, identifies public amenities and infrastructure to support growth in the area, including both short-term and long-term priorities in and around the plan area. Priorities for the first 10 years include:


- Increasing the supply of affordable housing 550 social housing, 190 below market rental and 1,500 secured market rental units.
- New childcare facilities Up to 360 additional spaces for 0-4 year olds, and 195 out-of-school care spaces.
- New and upgraded community and civic facilities New Oakridge civic centre, Hillcrest Community Centre fitness centre expansion, youth hub, land acquisition for new fire hall.
- New and upgraded parks and open spaces New Fraser River Park and parks on major project sites, upgrades to existing parks, six new plazas or open spaces.

• Transportation improvements – Complete Street designs on Cambie Street and other arterials, "car-light" Heather Street between 37th Avenue and 41st Avenue.

Heritage – Allocate 5% of cash CAC revenues to support funding for the conservation of heritage resources City-wide, and Cambie Corridor on-site conservation.

PUBLIC BENEFITS IMPLEMENTATION TRACKING CAMBIE CORRIDOR PLAN (2018) – North of 57th Ave^a

Updated Year-End 2018



PUBLIC BENEFITS ACHIEVED - North of 57th Avea

Ca	ategory	Anticipated Public Benefits (+) °	Completed (•) or In Progress (○)	% ^d
	Housing⁵	+ 2,250 additional social housing units + 4,700 secured market rental units + 400 below-market rental units	9 social housing units 58 secured market rental units 46 social housing units 162 secured market rental units	5%
ė	Childcare	+ 1,080 spaces for all age groups	Restoration of outdoor play area at 8 Oaks Acorn childcare	0%
	Transportation/ Public Realm	Upgrade/expand walking and cycling networks Complete Street design on Cambie St. and major streets "Car-light" greenway on Heather St.	Traffic calming 45th Avenue Bikeway	10%
al	Culture	+ 5 new artist studios	Public art from rezonings	N/A
<u>&</u>	Civic/Community	Oakridge Civic Centre (includes renewal and expansion of Seniors' Centre) Oakridge Library renewal and expansion Additional library branch Hillcrest Community Centre – Fitness centre expansion Fire Hall #23 Community Policing Centre		0%
<u> </u>	Heritage	+ 5% allocation from cash community amenity contributions in Cambie Corridor	Heritage conservation (James Residence and Wong Residence) 5% allocation from cash community amenity contributions in Cambie Corridor	5%
À	Social Facilities	+ Additional Seniors' Centre + Youth Hub + Non-profit organziation centre		0%
	Parks	New parks on large sites Queen Elizabeth Park Master Plan and Phase 1 upgrades 6 plazas and enhanced open spaces Neighbourhood park improvements	Upgrades to Riley Park and Hillcrest Park Lillian To Park	5%

EXPLANATORY NOTES

The Public Benefits Implementation Tracker assists in monitoring progress toward the delivery of public benefits anticipated from the community plans. Data in this tracker reflects activity within the plan boundaries since Plan approval.

Population Growth

Base population is determined by the latest census year available when the Plan was approved. Projected growth numbers are determined by the numbers quoted in the Plan (if available). Growth is calculated by taking the difference between the latest census year and the base population and adding an estimate based on floor area completed between the latest census and the present quarter.

Development Activity

The Development Activity Chart tracks projects with 3 or more housing units and includes Development Permits, Building Permits, rezoning applications and enquiries:

- "Completed" projects have achieved Building Permit completion.
- "Under Construction" projects have achieved Building Permit issuance, but have yet to be completed.
- "Approved" projects include rezoning applications approved by Council and Development Permits that have been approved
 by the City. Any rezoning applications approved by Council that advance into the Development Permit stage are still counted
 as "Approved" projects until it achieves Building Permit issuance.
- "In review" projects include any rezoning applications, enquiries, or Development Permits that are under review by the City.

Recent rezoning approvals listed in this section reflect the last five rezonings (excluding minor text amendments) approved by Council within the last five years in the plan area.

Public Benefits Achieved

Public benefits that have either been completed or are under construction are included in this section. In addition, this tracker provides some insight on the progression of Major Projects or other City programs.

Other Notes

- ^a The Cambie Corridor Plan was a three-phase plan with its final phase approved in 2018. Phase 2 of the Cambie Corridor Plan was approved in 2011 and included land use policies for key sites and arterials. Monies collected between Phase 2 and Phase 3 were allocated/spent corridor-wide through the interim public benefits strategy. Benefits delivered south of 57th Ave include: affordable housing site; 2 childcare locations; new Family Place; 2 artist studios; and land acquisition toward Marpole Civic Centre.
- ^b Gross numbers of units reported. In some instances, existing units may be demolished and replaced with new units. These numbers represent units that have been replaced and any additional units included as a part of new developments.
- ^c See chapter 13 of the <u>Cambie Corridor Plan</u> for detailed information about the City's commitments to deliver public benefits along the Cambie Corridor.
- ^d Percentages reflect estimated progress toward overall Public Benefits Strategy targets outlined in chapter 13 of the <u>Cambie Corridor Plan</u>.

976 West 52nd Avenue and 6822-6868 Oak Street PUBLIC BENEFITS SUMMARY

Project Summary

Rezoning to RM-8AN District to facilitate a townhouse development.

	Current Zoning	Proposed Zoning
Zoning District	RS-1	RM-8AN
FSR (site area = 3,844 sq. m / 41,377 sq. ft.)	0.7	1.2
Floor Area (sq. ft.)	28,964 sq. ft	49,652 sq. ft.
Land Use	Single-Family Residential	Multi-Family Residential

Summary of development contributions expected under proposed zoning¹

City-wide DCL	\$209,531
City-Wide Utilities DCL	\$115,193
Density Bonusing Contribution	\$1,137,840
TOTAL VALUE OF PUBLIC BENEFITS	\$1,462,564

¹ Assumes development maximizes allowable density. Based on rates in effect as at September 30, 2018. Rates are subject to future adjustment by Council, including annual inflationary adjustments.

976 West 52nd Avenue and 6822-6868 Oak Street APPLICANT, PROPERTY, AND DEVELOPMENT PROPOSAL INFORMATION

Property Information

Address	Property Identifier (PID)	Legal Description
976 West 52nd Avenue	009-061-720	Lot 1, Block 880, District Lot 526, Plan 11706
6822 Oak Street	009-061-789	Lot 2, Block 880, District Lot 526, Plan 11706
6836 Oak Street	009-061-797	Lot 3, Block 880, District Lot 526, Plan 11706
6850 Oak Street	009-061-801	Lot 4, Block 880, District Lot 526, Plan 11706
6868 Oak Street	010-031-898	Lot 5, Block 880, District Lot 526, Plan 9628

Applicant Information

Architect	Listraor (West 52nd) Homes Ltd.
Property Owner	Listraor (West 52nd) Homes Ltd.

Site Statistics

Site Area	3,844 sq. m (41,377 sq. ft.)	3,844 sq. m (41,377 sq. ft.)
-----------	------------------------------	------------------------------

Development Statistics

·	Permitted Under Existing Zoning	Development Permitted Under Proposed Zoning
Zoning	RS-1	RM-8AN
Uses	One-Family (Residential)	Multiple Dwelling (Residential)
Max. Density	0.70 FSR	Up to 1.2 FSR
Floor Area	2,691 sq. m (28,964 sq. ft.)	Up to 4,613 sq. m (49,652 sq. ft.)
Height	10.7 m (35 ft.)	Up to 3 storeys (at the street): 11.5 m (37.7 ft.)
Unit Mix	n/a	as per RM-8AN District
Parking, Loading And Bicycle Spaces	as per Parking By-law	as per Parking By-law